




中國人壽大廈一樓裝修工程

1st Reply for Queries from Tenderers

Reply Date

22-May-25

Refer to some tenderers have the following tender queries, please also find our replies in [blue](#) for your information.

	Queries from Tenderers	Replies
1	<p>Tender Drawing Partition (Legend Code: P3) SOR without item "NCO ACOUSTIC BARRIER MAT", please clarify.</p> 	<p>Please ensure that the acoustic mat is included in your SOR</p> <p>Amended schedules of rate are issued in tender addendum no. 2</p>
2	<p>SOR – Schedule 2.3.2 Please provide details or materials information for the suspended mounted ceiling features.</p> 	<p>The ceiling feature will be 60mm high MT1 frame around the edge. The finishes will be a 12mm thick acoustic panel.</p> <p>Main Contractor is responsible to submit the shop drawing, fixing method, and RSE-endorsed structural loading calculations for review and approval by the Project Manager and Designer.</p> <p>Amended drawings are issued in tender addendum no. 2</p>
3	<p>SOR – Schedule 2.7.3 Please provide details or materials information for the wall mounted artwork with frame (Legend Code: S-03).</p> 	<p>Provisional sum for S-03 is updated in the amended schedules of rate are issued in tender addendum no. 2</p>
4	<p>For Technical Spec. (Appendix 3): #B2.12 – area needed to install the motion sensor lighting control system , pls specify #B2.13 – area to be covered w/the timer lighting control system. pls specify #B2.14 – Pls clarify if the essential power and new emergency power is needed #B2.16 – pls clarify the PA & mobile phone antenna is for inside the premise or public area as we couldn't see any existing PA on site #C.1.5.1.5 – pls clarify the control for the dimmer (i.e by lighting control system / manually) #C.3.9.8 & C.3.9.9 – pls clarify the requirement of the automatic control system for AC (i.e is it required to control schedule duties & temp.) #C.3.10.4 – any sound test is required . pls clarify</p>	<p>Scope of works for B2.12, B2.13, B2.14 and B2.16 are not required. Appendix 3 - E&M Technical Specification is updated, please refer to the tender addendum no. 2.</p> <p>For Section C – Particular Specification, MC should comply with the standards listed or those indicated in the tender.</p> <p>Items not specified at this stage are considered for reference only and are not required at the moment. However, please bear in mind that these items may be required at a later stage.</p> <p>Main Contractor is also required to provide all relevant information, documents, test reports, Lab test data or any other information or test to meet the expectations of the Client, PM, and Designer.</p>
5	<p>For Drawings, material & SOR: <u>Partitioning work</u> #Code P1 – the insulation material not match w/SOR#2.2.1. pls clarify #PSB – the legend & location for 50 x 3 Flat Bar, acoustic mat 3mmthk not match in pages of drawings and it doesn't mention in SOR#2.2.7. pls clarify the installation method & required (see attached drawings highlighted)</p>	<p>Insulation material is 80kg/m3 rockwool, tender drawings are updated and issued in tender addendum no. 2.</p> <p>P3 and P5 Please ensure that the acoustic mat is included in your SOR, Amended schedules of rate are issued in tender addendum no. 2</p> <p>For SOR# 2.2.7 – PSB, if it is not indicated in the drawings, you may leave it blank.</p>
6	<p>For Drawings, material & SOR: Ceiling work #SOR2.3.2 & DWG 06.01-01 –finishes for acoustic ceiling feature not found in material schedule. Pls clarify</p>	<p>The ceiling feature will be 60mm high MT1 frame around the edge. The finishes will be a 12mm thick acoustic panel.</p> <p>Main Contractor is responsible to submit the shop drawing, fixing method, and RSE-endorsed structural loading calculations for review and approval by the Project Manager and Designer.</p> <p>Amended drawings are issued in tender addendum no. 2</p>